BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41598/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Pot hole filling to Roads in Ward No.06 (Thanisandra) Surrounding area Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MANJUNATH K	
				In Figures	In Words
1	1281.17	KSRRB- M 3000-2: Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per s[ecifications. MORTH Specification No. 3003 (Page No. 265/ Item No.35.20, PWD SR 2018-19	Sqm	26.62	Rupees Twenty Six and Sixty Two Paise Only
2	192.18	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 155/ Item No. 20.18/ PWD SR 2018-19	Cum	1793.15	Rupees One Thousand Seven Hundred Ninety Three and Fifteen Paise Only
3	1281.17	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications MORTH Specification (Page No. 259/Itm No.35.5) PWD SR 2018-19	Sqm	328.76	Rupees Three Hundred Twenty Eight and Seventy Six Paise Only

Manjunath-K

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92